BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Providing Steel Name boards at Ravindranagara & Mallasandra, in Ward -13 in Shettyhalli Sub- Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, **in hard soil** not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	185.49	194.40	Rupees One Hundred Ninety Four and Forty Paise Only
2	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	37.10	3431.22	Rupees Three Thousand Four Hundred Thirty One and Twenty Two Paise Only
3	Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	m	20.87	4319.00	Rupees Four Thousand Three Hundred Nineteen Only
4	Providing and fixing in trenches galvanized / mild steel tubes (medium grade) 65mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments complete as per specifications.	m	801.50	474.12	Rupees Four Hundred Seventy Four and Twelve Paise Only
5	Providing and fixing 1mm thick M.S. sheet sliding shutters with frame and diagonal braces of 40x40x6 mm angle Iron 3.15mm thick M.S. Gusset plates at junctions and corners, 25mm dia pulley, 40x40x6 mm angles and T iron guide rail top and bottom respectively with handles, stoppers and locking arrangements etc., including applying a priming cost of red lead paint cost of materials, labour, HOM of machinery complete as per specifications.	Sqm	103.05	2523.96	Rupees Two Thousand Five Hundred Twenty Three and Ninety Six Paise Only

Signature Of The Contractor

Executive Engineer

KRIDL, Dasarahalli Zone, Bangalore

6	Applying red lead ready mix priming coat over mew steel or other metal surface including preparing the surface after thoroughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushers, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.	Sqm	286.25	21.84	Rupees Twenty One and Eighty Four Paise Only
7	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	286.25	72.50	Rupees Seventy Two and Fifty Paise Only
8	Painting New letter and figures of any shade with synthetic enamel paint black of any other approved colour to give an even shade complete as per specifications.	cm	103050.00	0.57	Fifty Seven Paise Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 62.00	cum	185.49	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Signature of the Contractor

Executive Engineer
Dasarahalli Division